

QBS GROUP Pty Ltd T/A QUALIFIED BUILDING SERVICES															
PO BOX 487, GORDON, NSW, 2072															
Phone: (02) 9499 5141 / Fax: (02) 9499 4954															
email: info@qbsgroup.com.au															
QBS - BUILDING QUANTITY SURVEY - SAMPLE															
N#	Item	Description	Included	Unit	Qty	Rate	Item Totals	PC Allowance	Comments builder	Supplier	Trading	TRADER SUPPLIER	TRADER INSTALLER	ESTATUS INSTALLATION	ESTATUS SUPPLIER
	1	Preliminaries Overheads													
1	1.01	Project manager-Site Supervisor-Building margining	YES	LS	1.00						QBS	Jose Rivas			
2	1.02	Site survey (site set-out and Final certificate)	YES	LS	1.00						SURVEY at the end				
3	1.03	Council/Private Certifier Authority (PCA) permits	NO	LS	0.00				DA COUNCIL / CERTIFIER FEE FOR CC		CERTIFIER				
4	1.04	All engineering and PCA inspections	NO	LS	0.00				QBS GROUP - CLIENT		CERTIFIER & PROFESSIONALS-TRADERS PROVIDING CERTIFICATIONS				
5	1.05	Home Warranty insurance	NO	LS	0.00				H.W.I. FROM BUILDERS		QBS				
6	1.06	Temporal Site fencing and barricades	YES	M1	14.00						QBS				
7	1.07	Tree protection for main tree as required from Council.	YES	LS	1.00						QBS				
8	1.08	Temporary toilet & basin	YES	LS	1.00						QBS				
9	1.09	Sediment control as detailed on Stormwater and Environmental Management Plan.	YES	LS	1.00						QBS				
10	1.10	Scaffold establishment (delivery, erect, dismantle)	YES	LS	1.00						SCAFFOLDER				
11	1.11	Crane hire	YES	LS	1.00				Allowance for 3 times		CRANE SUPPLIER				
12	1.12	Site kit (PPE and associated site tools)	YES	LS	1.00				OHSE & SWM - First ID		QBS				
13	1.13	All site waste removal for duration of project	YES	LS	1.00										
14	1.14	Final clean allowance	YES	LS	1.00						CLEANER				
15	1.15	Special structure to protect aquarius inside working area. Include steel structural frame and Particle board Yellow Tongue sheets 19 mm, and sealed with heavy duty plastic	YES	LS	1.00						CARPENTRY				
16	1.16	Special cover to protect shelves inside working area with micro fibro plastic.	YES	LS	1.00						QBS				
17	1.17	Disconnection and connection of main power from electrician licensed. Include connection with external electric plant.	YES	LS	1.00						ELECTRICIAN				
18	1.18	Hire of Portable Electric Power Plant (Generator) for work during construction	NO	LS	0.00						POWER SUPPLIER				
19	1.19	Supply and install of consumer main from the main pole to the permanent meter box	YES	LS	1.00										
	2	Demolition & Alterations													
20	2.01	ASBESTOS REMOVAL of whole structure of existing garage single story, timber framed and metal sheed, if existing.	YES	M2	39.14						ASBESTOS REMOVALISTS				
19	2.02	Demolition of whole structure of existing garage single story, timber framed with brick external walls, reinforced concrete ground. Include shed with metal roof and walls	YES	M2	62.54						DEMOLITION COMPANIES				
20	2.03	Partial demolition of existing pathway and driveway of concrete ground slab 150mm - Area of Building Extension	YES	M2	69.30						DEMOLITION COMPANIES				
21	2.04	Partial demolition of existing pathway and driveway of concrete ground slab 150mm - External Areas	YES	M2	91.33										
22	2.05	Partial Demolition of external brick walls of different thickness and locations as detailed in construction drawings.	YES	M2	20.59						CARPENTRY				
23	2.06	Demolition of external stud walls with fibro cement sheeting	YES	M2	38.35						CARPENTRY				
24	2.07	Disassembly of existing roller door	YES	M2	7.50						CARPENTRY				
25	2.08	Demolition of existing Awning in shops. Include disassembly of metal sheets and structures	YES	M2	51.19						CARPENTRY				
26	2.09	Demolition of existing fibrous plaster suspended ceiling including suspension grid	YES	M2	77.88						CARPENTRY				

27	2.1	ASBESTOS REMOVAL of existing asbestos suspended ceiling including suspension grid (SHOP 2 - aquarium)	YES	M2	72.00										ASBESTOS REMOVALISTS		
28	2.11	Demolition of Pitch roof, including strip roof covering of corrugated iron sheets and battens and taking down timber roof framing and eaves	YES	M2	75.53										CARPENTRY		
29	2.12	Demolition of Flat roof, including strip roof covering of felt or composition roofing and taking down timber roof framing and eaves	YES	M2	84.48										CARPENTRY		
30	2.13	Partial demolition of roof structure. Roof tiles will be storage on site to be reused.	NO	M2	0.00												
31	2.14	Dismantle of Hot Water Tank. Include installation of provisional pipes and connections until final location	NO	LS	1.00												
32	2.15	Strip out of joinery - kitchen & Bathrooms	NO	LS	1.00												
33	2.16	Plumbing fitting to be removed in bathroom and kitchen areas.	YES	EA	4.00										CARPENTRY		
34	2.17	Removal and disposal of Single and double Doors as required for construction of extension. Include timber / steel door frame in brick / framed wall	YES	EA	5.00										CARPENTRY		
35	2.18	Removal and disposal of timber / steel frames and Windows as required for construction of extension.	YES	EA	21.00										CARPENTRY		
36	2.19	Electrical disconnection and sealing off Light Points	YES	EA	20.00										ELECTRICIAN		
37	2.2	Electrical disconnection and sealing off Power Points	YES	EA	11.00										ELECTRICIAN		
38	2.21	Temporary protection of roof openings with Tarpaulins	YES	M2	72.00										QBS		
39	2.22	Removal and disposal of debris on BINS - brick, concrete, rubble, timber, lining material, sheets roofing and the like. (See item 1.13)	YES	M3	82.56										WASTE REMOVALIST		
40	2.23	Gravel trap at the entrance of construction site	YES	M3	1.40										QBS		
41	2.24	Supply and install of Anchorage in existing ground slab inside Shop 1 for stairs	YES	LS	1.00										CARPENTRY		
3 Excavation and preparation																	
42	3.01	Clear site vegetation and disposal on BINS. Include light vegetation up to 500 m2	YES	M2	119.90										EXCAVATION Co		
43	3.02	Excavate to remove vegetable soil average 150mm deep spread and level on site, up to 500 m2	YES	M2	119.90										EXCAVATION Co		
44	3.03	Excavate trenches up to 1.00 m deep in sand or light soil - For Sewage main	YES	M3	7.55										BUILDER		
45	3.04	Excavate pits up to 1.00 m deep in sand or light soil	NO	M3	0.00												
46	3.05	Detail excavation of pits and trenches in confined spaces in soil by hand as detailed on drawings for Footings	YES	M3	16.69										BUILDER		
47	3.06	Excavate for thickening to ground slabs in soil by hand including forming both sides to slope as detailed on drawings for Footings and slabs - FOR BUILDING EXTENSION	YES	M3	3.02										CARPENTRY		
48	3.07	Excavate for thickening to ground slabs in soil by hand including forming both sides to slope as detailed on drawings for Footings and slabs - FOR EXTERNAL AREAS	YES	M3	6.46										EXCAVATION Co		
49	3.08	Supply and install of plastic membrane polythene film 200mm. Include all laps and joining	YES	M2	66.82										CARPENTRY		
4 Pest Control																	
50	4.01	Termite protection (GF extension & plumbing penetration in GF new Bathroom)	YES	LS	1.00				Footing, Wall-beam & pipe penetrations						PEST CONTROL		
51	4.02	Ant Capping installation Type galvanised sheet steel	NO	LS	1.00				Strip dwarf walls & piers								
5 External Works																	
52	5.01	In Situ concrete paving - 20 MPa concrete including SL72 fabric reinforcement, expansion joints, edge forms and broomed finish for paving 150mm thick	YES	M2	116.81										CONCRETER		
53	5.02	In Situ Permeable bitumen paving - proposed concrete brick or block paving laid on prepared foundation type Interlocking 225 x 112 x 80mm with 75mm thick compacted sand bed	YES	M2	79.20										LANDSCAPER - TURF		
54	5.03	Cast In Situ concrete including reinforcement, formwork and surface finish of Box Drain 300mm wide x 250mm deep internally with 100mm thick bottom and sides	YES	M1	202.00										CONCRETER		
55	5.04	Top soil spread in layers over the ground, raked and levelled 300 mm thick	YES	M2	16.95										LANDSCAPER - TURF		
56	5.05	Supply of Turf, 400mm wide roll turf aid, rolled and watered for two weeks	YES	M2	8.30										LANDSCAPER - TURF		

112	14.03	Installation and finish of timber flooring on particleboard - Interior areas. (Timber flooring allowance for material: Blackbutt - selected grade: material \$75/m ²).	YES	M2	93.39						FLOORING INSTALLER				
113	14.04	Installation of timber flooring on existing timber floor. Including removal of existing skirtingboard and supply and install 17 mm plywood sheets on top of the existing timber floor. (New timber flooring is not included)	NO	M2	0.00										
15 Internal Linings (Walls & Ceilings)															
114	15.01	Supply and install wall lining with 10mm thick Plasterboard over Timber wall framing.	NO	M2	0.00										
115	15.02	Supply and install wall lining with 13mm thick Plasterboard over Steel wall framing (Aluminium studs).	YES	M2	245.11						PLASTERER (GYPROCK INSTALLATOR)				
116	15.03	Supply and install wall lining with 16mm thick Fire Rated Plasterboard flush finish over steel wall framing (Aluminium studs).	YES	M2	239.77						PLASTERER (GYPROCK INSTALLATOR)				
117	15.04	Supply and install ceiling system with 10mm platerboard	YES	M2	211.86						PLASTERER (GYPROCK INSTALLATOR)				
118	15.05	Supply and install ceiling system with 13mm platerboard for commercial purpose. Include a concealed suspension system	YES	M2	229.27						PLASTERER (GYPROCK INSTALLATOR)				
119	15.06	Supply and install ceiling sheet system type FRL with DOUBLE 13mm platerboard installed under timber joist system.	YES	M2	229.27						PLASTERER (GYPROCK INSTALLATOR)				
120	15.07	Supply and install cornices (matching existing cornices where applicable)	YES	M1	164.80						PLASTERER (GYPROCK INSTALLATOR)				
121	15.08	Aquacheck in wet areas & ceiling outdoor. (Rear Verandah, Balcony & Bathrooms)	YES	M2	49.04						PLASTERER (GYPROCK INSTALLATOR)				
122	15.09	6mm fibrocement or vilboard in new lining walls - Wet areas. (Bathrooms & Kitchen).	YES	M2	132.88						PLASTERER (GYPROCK INSTALLATOR)				
16 Joinery															
123	16.01	Supply New Skirting boards rounded or splayed fixed to timber type 150 x 25mm local hardwood or MD Fibreboard (similar to existing where applicable).	YES	M1	376.49						CARPENTRY				
124	16.02	Replacement some sections-old skirting boards	NO	M1	0.00										
125	16.03	Supply and intall Handrails type plain with rounded edges 150 x 50mm fixed to wall	NO	M1	0.00										
126	16.04	Supply and install Kitchen joinery	YES	M1	0.00					if required approx. \$ 24,500 Only Cabinets. Installed.	CABINETS INSTALLER				
127	16.05	Supply of Ensuite & Bathroom vanities, including vanity bench and cupboard unit of 600mm deep x 900mm high, cupboards and drawers under, plastic laminate finish and prepared to receive basin	YES	M1	1.80						CARPENTRY				
128	16.06	Install of Ensuite & Bathroom vanities	YES	LS	1.00					Accessories & Vanities is not included	CARPENTRY				
129	16.07	Supply and install built-ins wardrobes type 600mm deep x 2400mm high with shelves, hanging rails, sliding doors and freestanding: Natural timber veneer finish	YES	M1	18.15						CABINETS INSTALLER				
130	16.08	Supply and install laundry joinery if required. Tub Cabinet - Bench	YES	M1	5.05						CABINETS INSTALLER				
131	16.09	Supply and install bookshelf and others if required	NO	M1	0.00										
17 Windows and doors															
132	17.01	Supply and installation of external ALUMINUM FRAME single glass windows type Custom Made Casement style according with drawings.	YES	M2	9.24						ALUMIN WINDOWS (SUPPLIER)				
133	17.02	Supply and installation of external ALUMINUM FRAME single glass windows type Custom Made Awning style according with drawings.	YES	M2	14.45						ALUMIN WINDOWS (SUPPLIER)				
134	17.03	Supply and installation of external ALUMINUM FRAME single glass windows type Custom Sliding style according with drawings.	YES	M2	9.65						ALUMIN WINDOWS (SUPPLIER)				
135	17.04	Supply and installation of external ALUMINUM FRAME single glass windows type Custom Made with Fixed light according with drawings.	YES	M2	5.02						ALUMIN WINDOWS (SUPPLIER)				
136	17.05	Supply and installation of Clear anodised aluminium shop fronts, standard section, glazed with 10mm toughened safety glass	YES	M2	28.42						BALUSTRADING SUPPLY & INSTALL				

208	26.10	Pipework installation in COPPER for HOT WATER supply in KITCHEN, KITCHENETTE AND LAUNDRY. Include main tap and fittings such as reducers, bends, tees, junction and inspection openings for sink & dish washer. Outlet fittings not included	YES	LS	1.00										PLUMBING			
209	26.11	Pipework installation for sewage in WC, SHOWER and BASIN Include fittings such as reducers, bends, tees, junction and inspection openings . Outlet fittings not included	YES	LS	1.00										PLUMBING			
210	26.12	Pipework installation for sewage in LAUNDRY Include fittings such as reducers, bends, tees, junction and inspection openings. Outlet fittings not included	YES	LS	1.00										PLUMBING			
211	26.13	Pipework installation for sewage in in KITCHENS & KITCHENETTES. Include fittings such as reducers, bends, tees, junction and inspection openings for sink & dish washer. Outlet fittings not included.	YES	LS	1.00										PLUMBING			
212	26.14	Pipework installation for Ventilation pipe.Include fittings such as reducers, bends, tees, junction and inspection openings	YES	LS	1.00										PLUMBING			
212	26.15	Adjust plumbing to existing construction. Plumbing Connection works from new construction to existing sewage and water supply system	YES	LS	1.00										PLUMBING			
213	26.16	Supply and installation of stormwater system Including rain water tank. According with drawing plans.	YES	LS	1.00										PLUMBING			
214	26.17	Supply and Install Electric Main Pressure HWS	YES	LS	1.00													
215	26.18	Gas mains upgrade	NO	LS	1.00													
216	26.19	Pipework installation for Gas supply	NO	LS	1.00													
27	Electrical Services																	
217	27.01	Supply and Installation of Consumers Mains to Main Board for new construction	NO	M1	0.00													
218	27.02	Intallation of underground conduit from the main pole to the new permanent meter box	YES	M1	31.00										ELECTRICIAN			
219	27.03	Supply and install of Temporal Power Meter and power Points on existing Main Box	NO	LS	0.00													
220	27.04	Supply and install New Power Meters. Include wiring from Main Power	YES	EA	5.00										ELECTRICIAN			
221	27.05	Supply and installation of custom built switchboard MSB for residential and commercial units. Include new wiring, breakers and safety switch	YES	EA	5.00										ELECTRICIAN			
222	27.06	Supply and Install Exterior Lighting points; including luminaires for car park and driveways - Common Areas	YES	PT	13.00										ELECTRICIAN			
222	27.07	Supply and Install Lamp ceiling points. Include wiring conduit, switch but exclude light fittings	YES	PT	135.00										ELECTRICIAN			
223	27.08	Wall lamp points for retail shop and residential units - Indoor & Outdoor	YES	PT	20.00										ELECTRICIAN			
224	27.09	Dimmers - Fittings by owners.	NO	PT	0.00													
225	27.10	Suply and install Power points type twin power outlet on internal areas	YES	PT	81.00										ELECTRICIAN			
226	27.11	Supply and install single phase hot water system circuit for residence use	YES	PT	4.00										ELECTRICIAN			
227	27.12	Supply and install Single Phase 5KW oven circuit for residence use	YES	PT	2.00										ELECTRICIAN			
228	27.13	Supply and install Single Phase 6KW cooking top circuit for residence use	YES	PT	2.00										ELECTRICIAN			
229	27.14	Supply and install of weatherproof twin Power points on external areas	YES	PT	8.00										ELECTRICIAN			
230	27.15	Supply and Install Switch points	YES	PT	33.00										ELECTRICIAN			
231	27.16	Supply and install Exhaust fans points and switch points for a combined light and radiant heat-globe unit. Excludes unit and switch	YES	PT	4.00										ELECTRICIAN			
232	27.17	Supply and Install Power point for Internal Air conditioning unit (splitter)	YES	PT	10.00										ELECTRICIAN			
233	27.18	Supply and Install Power point for Outdoor Air conditioning unit (compressor) - 15 amp power outlet	YES	PT	4.00													
234	27.19	Supply and install Luminaires - Single 36W fluorescent batten with prismatic lens	YES	EA	41.00										ELECTRICIAN			
235	27.20	Supply and install of Luminaires - LED Lights from 22W to 72W in plastic or metal finish to be Advised	YES	EA	20.00										ELECTRICIAN			
236	27.21	Supply and install Luminaires - LED Downlight (high quality) - 7 Watts	YES	EA	48.00										ELECTRICIAN			
237	27.22	Supply and install Luminaires - Exterior and Interior Reflector Wall lights (single)	YES	EA	21.00										ELECTRICIAN			
238	27.23	Supply and install Heater - Type 275W 4 Heat Lamps and exhaust fan with 3m of flexible ducting	YES	EA	4.00										ELECTRICIAN			
239	27.24	Supply and instal Fans - In-line exhaust fan and ducted kit with flex duct, inlet and outlet 150mm dia centrifugal, 6m duct 500 cum/hr fan	YES	EA	2.00										ELECTRICIAN			

